BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

BBMP/2023-24/OW/WORK_INDENT2657

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/16/2023-24 Dated: 21-02-2024

APPROVED TENDER SCHEDULE - B

Item-02

Name of Work:-Construction of Additional floor to Govt. Primary school at Puttenahalli Colony in ward No 02

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
1	Demolishing cement concrete manually/ by mechanical means including disposal of material to the appropriate disposal area as per direction of Engineer-in-charge. Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum. (Tipper 10 m3) Cost of Haulage Excluding Loading and Unloading Case-1 : Surfaced Road Taking output 10 t load and lead 10 km = 100 t.km	Cum	15.75	2190.90	Two Thousand One Hundred Ninety Paise Ninety Only
2	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material to the appropriate disposal area as per direction of Engineer-in-charge. In cement mortar. Loading and Unloading of Stone Boulder/Stone aggregates/Sand/Kankar/Moorum. (Tipper 10 m3) Cost of Haulage Excluding Loading and Unloading Case-1 : Surfaced Road Taking output 10 t load and lead 10 km = 100 t.km	Cum	34.50	1473.30	One Thousand Four Hundred SeventyThree Paise Thirty Only
3	Earth work excavation by manual means for drains,canals, waste weir draft, approach channels, key trench, foundation of Bridges and such similar works, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, excavated surface leveled and sides neatly dressed disposing off or leveling the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage & other appurtenances required to complete the work. In ordinary/soft rock without blasting upto 1.5 m depth	Cum	188.07	338.40	Three Hundred ThirtyEight Paise Fourty Only
4	Providing and injecting chemical emulsion for Pre-constructional Anti-Termite Treatment, creating continuous chemical barrier under and around the column pits, walls, trenches, basement excavation, top surface of the plinth filling, junction of wall and floor, along the external perimeter of building, expansion joints, over the top surface of consolidated earth on which apron is to be laid, surrounding of pipes and conduits with Chlorpyriphos 20% E.C. / Lindane 20% E.C. @ 3.19 l/m2 including cost of chemical, diluting in water to one percent concentration, labour, usage charges of machinery, complete as per specifications.	Sqm	138.13	133.60	One Hundred ThirtyThree Paise Sixty Only
5	Providing and Filling in foundation with granite / trap broken metal 100mm. and down size & with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift complete as per specifications.	Cum	30.74	3035.80	Three Thousand ThirtyFive Paise Eighty Only

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
6	Providing and laying in position plain cement concrete Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications.	Cum	37.01	6778.90	Six Thousand Seven Hundred SeventyEight Paise Ninety Only
7	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum	54.76	7231.70	Seven Thousand Two Hundred ThirtyOne Paise Seventy Only
8	Providing and laying in position Cement Concrete for all Foundation works. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticizers laid in finished layers, well compacted using needle vibrators, including all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all the other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	25.19	7386.90	Seven Thousand Three Hundred EightySix Paise Ninety Only
9	Providing and laying in position Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	6.53	12191.90	Twelve Thousand One Hundred NinetyOne Paise Ninety Only
10	Providing and laying in Cement Concrete for all Basement & surface level works, return walls, retaining walls, sunken floors etc. The granite/trap/ basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	9.13	11002.10	Eleven Thousand Two Paise Ten Only
11	32A DP Switch	Each	2.00	335.50	Three Hundred ThirtyFive Paise Fifty Only
12	6/16A Universal Socket	Each	10.00	242.80	Two Hundred FourtyTwo Paise Eighty Only
13	Supplying and fixing 32Amps security and energy saving DP switch with key tag suitable to operate on 230 Volts, 50Hz AC supply &completely wired on existing box (ELE SR 2023-24 Page-9, Item-3.7)	Each	5.00	664.70	Six Hundred SixtyFour Paise Seventy Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
14	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. a. 1 sqmm. (ELE SR 2023-24 Page-9, Item-3.7)	m	150.00	19.60	Nineteen Paise Sixty Only
15	1.5Sqmm	m	150.00	26.80	TwentySix Paise Eighty Only
16	6Sqmm	m	75.00	94.70	NinetyFour Paise Seventy Only
17	10Sqmm	m	30.00	171.80	One Hundred SeventyOne Paise Eighty Only
18	16Sqmm	m	50.00	327.20	Three Hundred TwentySeven Paise Twenty Only
19	Supplying and fixing of PVC casing and capping on the wall or ceilng using necessary materials like bends, screws at an interval of 300mm .... Etc as required. a) 20mm (ELE SR 2023-24 Page-3, Item-1.8.1)	m	100.00	28.80	TwentyEight Paise Eighty Only
20	Supplying PVC/GI flexible conduit pip 20mm dia fixing on surface over inverted wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and either end of the pipe terminated completely. 20mm (ELE SR 2023-24 Page-3, Item-1.9.1)	m	100.00	19.60	Nineteen Paise Sixty Only
21	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	4.09	13167.50	Thirteen Thousand One Hundred SixtySeven Paise Fifty Only
22	Extra for supplying 4mm thick white plastic plate and covering for junction boxes of size 110mm conduit using necessary machine screws. b) 110mm	Nos	15.00	21.60	TwentyOne Paise Sixty Only
23	Supplying a 50mm wooden plug, tapered from 50x50mm to 25x25mm and fixing by using binding wire before concreting a roof slap.	Nos	20.00	12.30	Twelve Paise Thirty Only
24	Supplying of 1 x 4 feet PVC Batten with integrated LED tube 20/22 W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI 80. Power Input 220 240V @ 50/60Hz & Power factor 0.9 along with CE approved. 2 years Warranty against any manufacturing defect working under standard electrical condition	Nos	30.00	710.00	Seven Hundred Ten Only
25	Supply of round/square recess/surface mounted rolling type LED Down light with ..... W GU 10 LED Lamp Rib Fabricated from diecast aluminium with white powder coated prewired to mains connector & has swivelling unit of aluminium die cast eye ball & LED Lamp position retained by circular wire spring, with Life of 25000 burning hours & 70% lumen maintenance with CRI 80. Power Input: 220-240V 50/60Hz & Power factor 0.9 along with CE approved. 2years Warranty against any manufacturing defect working under standard electrical condition LED square or round down light 10-12W	Nos	20.00	910.70	Nine Hundred Ten Paise Seventy Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
26	Supplying of Ceiling Fan with Capacitor rating As per guideline of BEE 5 star rating and IS:374/79 and also comply with IS: 1709/1984 with latest amendment, Rated voltage 220 V/50 Hz, Rated power input 48 W +/- 10 %, Rated current As per IS:374/79, Rated power factor 0.9 lagging(min), Rated speed 350 +/- 10% RPM, Rated air delivery 210 +/- 10% Cubic Meter Minimum, Rated service value 4.2 CMM / W, Three Blades of blade leaf 1.05 mm thick Aluminium Alloy sheet, Class B motor insulation, Bearing Two ball bearings, Top 6202, Bottom 6201, as per IS specification, Motor winding. Temp rise Shall not exceed 75 deg C over and ambient of 40 0C by resistance method at 245 V, Insulation resistance Shall not be less than Two Mega Ohms (2M Ohms), Leakage current Should not exceed 210 Micro Amp, Power input, W& current, Air Delivery & Fan Speed as per IS:374/1979 with latest amendment, 2 year manufacturer Warranty. 48" Sweep 5 Star (1200 mm)	Each	8.00	2754.60	Two Thousand Seven Hundred FiftyFour Paise Sixty Only
27	Supplying of 1440 rpm heavy duty exhaust fan with bracket blades suitable to operate on 230V 50Hz, AC Supply complete. 15" Sweep (450 mm) (ELE SR 2023-24 Page-30, Item-6.2.2)	Each	4.00	4574.90	Four Thousand Five Hundred SeventyFour Paise Ninety Only
28	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	10.80	12392.90	Twelve Thousand Three Hundred NinetyTwo Paise Ninety Only
29	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	20.16	11618.40	Eleven Thousand Six Hundred Eighteen Paise Fourty Only
30	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification.	Tonne	13.21	101256.40	One Lakh One Thousand Two Hundred FiftySix Paise Fourty Only
31	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	122.47	1482.80	One Thousand Four Hundred EightyTwo Paise Eighty Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
32	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	41.76	1393.40	One Thousand Three Hundred NinetyThree Paise Fourty Only
33	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x100x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	20.64	1249.60	One Thousand Two Hundred FourtyNine Paise Sixty Only
34	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	183.95	400.70	Four Hundred Paise Seventy Only
35	Providing 15 mm cement plaster with cement mortar 1:3 (1 cement:3 coarse sand) finished with a floating coat of neat cement on the rough side of single or half brick wall including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	215.98	414.30	Four Hundred Fourteen Paise Thirty Only
36	Providing 12 mm cement plaster with cement mortar 1:6 (1 cement:6 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	95.44	272.80	Two Hundred SeventyTwo Paise Eighty Only
37	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge..	Sqm	495.38	113.20	One Hundred Thirteen Paise Twenty Only
38	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :Water thinnable cement primer to give an even shade after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	183.95	60.00	Sixty Only
39	Finishing walls with textured exterior paint of required shade :New work (Two coats applied @ 3.28 L/10 m^2) over and including priming coat of exterior primer applied @ 2.20kg/10 m^2 to give an even shade after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	183.95	320.30	Three Hundred Twenty Paise Thirty Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
40	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications: Two coats applied on walls @ 1.25 L/10 m² over and including one coat of Special primer applied @ 0.75 L/10 m² with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (The gloss should be 50% @ 60 degree angle with 10 years life)	Sqm	311.43	178.80	One Hundred SeventyEight Paise Eighty Only
41	Providing and laying Cement concrete pavement with 1:2:4 for commercial & residential building floors, hardpaths, footpaths using 1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size, including finishing complete as per Engineer incharge.	Sqm	10.85	7545.20	Seven Thousand Five Hundred FourtyFive Paise Twenty Only
42	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per m2 including pointing in white cement mixed with pigment of matching shade complete.	Sqm	58.84	1251.90	One Thousand Two Hundred FiftyOne Paise Ninety Only
43	Providing and laying flooring and steps fine machine polished granite stone slabs 20 mm thick on cement mortar bed 1:6, 20 mm thick, and joints finished with cement mortar 1:3 over existing cement concrete bed , including cost of materials, mortar, labour, curing complete as per specifications.	Sqm	118.39	6030.80	Six Thousand Thirty Paise Eighty Only
44	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc.	Kgs	526.50	207.10	Two Hundred Seven Paise Ten Only
45	Providing & fixing of 3 track x 2 panel sliding windows made out of multi chambered UPVC(Matching to RAL 9016) sections and with minimum TiO2(Titanium Dioxide) at 6PHR with TPE(Thermo Plastic Elastomer) and lead free, gaskets grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the window frame. The outer frame having an overall size of 108mm width x 45mmheight with reinforcement of 1mm thickness and Sash with overall size of 39mm x 75mm with GI reinforcement of 2mm and mesh sash of size 37mm x 58mm. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 24 mm. Windows shall be provided with 6mm plain float glass, standard hardware& Multi point locking system with touch lock. Wall thickness of frame & sash shall be of 2mm-2.5mm. Maximum possible size 2419mm x 2200mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made)	Sqm	10.79	7622.20	Seven Thousand Six Hundred TwentyTwo Paise Twenty Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
46	Providing & fixing of louvered ventilator made out of multi chambered UPVC (Matching to RAL 9016) sections and with minimum TiO2 (Titan um Dioxide) at 6PHR with TPE(Thermo Plastic Elastomer) and lead free with gaskets -grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the ventilator frame. The frame having overall size of 39mm x 39mm with GI reinforcement of 1mm thickness. Louver clip in Aluminium (powder coated in white) will be used on the frame along with plastic parts for fixing the 4 mm pin head glass. Wall thickness of frame shall be 2mm.Maximum possible size 1000mm x1000mm.(The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made)	Sqm	0.89	6473.30	Six Thousand Four Hundred SeventyThree Paise Thirty Only
47	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, usage charges complete as per specifications.	Cum	0.12	156286.00	One Lakh FiftySix Thousand Two Hundred EightySix Only
48	Providing and fixing in position fully panelled Honne wood shutters for doors with stiles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and stiles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, usage charges complete as per specifications. (excluding cost of fixtures)	Sqm	4.20	8425.90	Eight Thousand Four Hundred TwentyFive Paise Ninety Only
49	Painting wood work with Deluxe Multi Surface Paint of required shade. Two coat applied @ 0.90L/10 m² over an under coat of primer applied @0.75 L/10 m² of approved brand and manufacture to give an even shade including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, sand papering and knotting , cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	8.40	156.20	One Hundred FiftySix Paise Twenty Only
50	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two coat applied @ 0.90L/10 m² over an under coat of primer applied @ 0.80 L/10 m² of approved brand and manufacture including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	8.40	157.30	One Hundred FiftySeven Paise Thirty Only
51	Providing & fixing factory made PVC Door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2 No.s of 150mm long brackets of 15x15mm M.S Square tube, the entire door frame to be reinforced with 19x19mm M.S Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size complete as per manufacturers specification & direction of Engineer-in-charge.	m	11.40	359.90	Three Hundred FiftyNine Paise Ninety Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
52	Providing & fixing 30mm thick factory made rigid foam Prelam Panelled Door Shutters made from M.S. tube of 19x19mm, 19 gauge for stiles and 15x15mm for top & bottom rails, covered with heat moulded Prelaminated PVC C Channel of 5mm thick sheet & 30x50mm wide to form stiles & 5mm thick & 75mm wide Prelaminated PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick, 20mm wide cross PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet Prelaminated on either side fitted in the M.S. frame, Sealed to the stiles & rails with PVC Designer beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75mm Aluminium hinges. do- with both side prelam	Sqm	3.15	2678.10	Two Thousand Six Hundred SeventyEight Paise Ten Only
53	Providing and fixing flush door shutter made out of solid core block board type, well seasoned , chemicaly treated hard wood battens and internal frame with minimum 45 mm wide wooden frame alround door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door useing liquid phenol formaldehyde resin as per IS specifications 2202 (part-I) 1991. from manufacturer complete as per spcification. -do- 35 mm thick both side commercial	Sqm	3.15	3760.20	Three Thousand Seven Hundred Sixty Paise Twenty Only
54	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in- charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.) including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	Kgs	84.00	639.50	Six Hundred ThirtyNine Paise Fifty Only
55	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	5.34	13299.20	Thirteen Thousand Two Hundred NinetyNine Paise Twenty Only
56	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	10.80	12516.90	Twelve Thousand Five Hundred Sixteen Paise Ninety Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
57	Providing and laying in position Cement Concrete for all Super structures of building , Road works, Water works, Irrigation works & super structure works of bridges upto 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers laid in layers, well compacted using needle vibrators. The cost includes all lead & lifts, cost of all materials, quality confirming to the requirements of relevant IS codes , labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M25 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	20.16	11734.60	Eleven Thousand Seven Hundred ThirtyFour Paise Sixty Only
58	Supplying, fitting and placing TMT FE 550 / 550D Steel Reinforcement including cost of all materials, machinery, labour, cleaning, straightening, cutting, bending, hooking, laping/welding joints, tying with binding wire / soft annealed steel wire and other ancilary operations complete as per drawing and technical specification.	Tonne	6.88	102268.90	One Lakh Two Thousand Two Hundred SixtyEight Paise Ninety Only
59	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x200x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	168.55	1497.60	One Thousand Four Hundred NinetySeven Paise Sixty Only
60	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	41.76	1407.30	One Thousand Four Hundred Seven Paise Thirty Only
61	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x100x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications.	Sqm	42.84	1262.10	One Thousand Two Hundred SixtyTwo Paise Ten Only
62	Providing 20 mm cement plaster of mix :1:4 (1 cement: 4 fine sand) to brick/stone masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	274.43	404.70	Four Hundred Four Paise Seventy Only
63	Providing 15 mm cement plaster with cement mortar 1:3 (1 cement:3 coarse sand) finished with a floating coat of neat cement on the rough side of single or half brick wall including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	215.98	418.40	Four Hundred Eighteen Paise Fourty Only
64	Providing 12 mm cement plaster with cement mortar 1:6 (1 cement:6 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	95.44	275.50	Two Hundred SeventyFive Paise Fifty Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
65	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per specifications and as per directions of Engineer in charge.. (KPWD SR 2023-24, V-II, Item No.8.51, Page No.50)	Sqm	585.85	114.30	One Hundred Fourteen Paise Thirty Only
66	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :Water thinnable cement primer to give an even shade after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (KPWD SR 2023-24, V-II, Item No.8.27, Page No.45)	Sqm	274.43	60.60	Sixty Paise Sixty Only
67	Finishing walls with textured exterior paint of required shade :New work (Two coats applied @ 3.28 L/10 m²) over and including priming coat of exterior primer applied @ 2.20kg/10 m² to give an even shade after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (KPWD SR 2023-24, V-II, Item No.8.29, Page No.45)	Sqm	274.43	323.50	Three Hundred TwentyThree Paise Fifty Only
68	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications: Two coats applied on walls @ 1.25 L/10 m² over and including one coat of Special primer applied @ 0.75 L/10 m² with paint of approved quality to give an even shade, after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. (The gloss should be 50% @ 60 degree angle with 10 years life) (KPWD SR 2023-24, V-II, Item No.8.33.1, Page No.46)	Sqm	311.43	180.60	One Hundred Eighty Paise Sixty Only
69	Providing and laying Cement concrete pavement with 1:2:4 for commercial & residential building floors, hardpaths, footpaths using 1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size, including finishing complete as per Engineer incharge. (KPWD SR 2023-24, V-II, Item No.9.4, Page No.59)	Sqm	10.85	7620.70	Seven Thousand Six Hundred Twenty Paise Seventy Only
70	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per m2 including pointing in white cement mixed with pigment of matching shade complete.	Sqm	58.84	1264.40	One Thousand Two Hundred SixtyFour Paise Fourty Only
71	Providing and laying flooring and steps fine machine polished granite stone slabs 20 mm thick on cement mortar bed 1:6, 20 mm thick, and joints finished with cement mortar 1:3 over existing cement concrete bed , including cost of materials, mortar, labour, curing complete as per specifications.	Sqm	119.91	6091.10	Six Thousand NinetyOne Paise Ten Only
72	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to openings /wooden frames with rawl plugs screws etc.	Kgs	526.50	209.20	Two Hundred Nine Paise Twenty Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
73	Providing & fixing of 3 track x 2-panel sliding windows made out of multi chambered UPVC(Matching to RAL 9016) sections and with minimum TiO2 (Titanium Dioxide) at 6PHR with TPE (Thermo Plastic Elastomer) and lead free, gaskets grey colour having isolated drainage and reinforced with Galvanized Iron profile through out the window frame. The outer frame having an overall size of 108mm width x 45mmheight with reinforcement of 1mm thickness and Sash with overall size of 39mm x 75mm with GI reinforcement of 2mm and mesh sash of size 37mm x 58mm. Coextruded Glazing bead for fixing of glass shall be of size 20mm x 24 mm. Windows shall be provided with 6mm plain float glass, standard hardware& Multi point locking system with touch lock. Wall thickness of frame & sash shall be of 2mm-2.5mm. Maximum possible size 2419mm x 2200mm. (The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made)	Sqm	10.79	7698.40	Seven Thousand Six Hundred NinetyEight Paise Fourty Only
74	Providing & fixing of louvered ventilator made out of multi chambered UPVC (Matching to RAL 9016) sections and with minimum TiO2 (Titan um Dioxide) at 6PHR with TPE (Thermo Plastic Elastomer) and lead free with gaskets grey colour having isolated drainage and reinforced with Galvanized Iron profile through-out the ventilator frame. The frame having overall size of 39mm x 39mm with GI reinforcement of 1mm thickness. Louver clip in Aluminium (powder coated in white) will be used on the frame along with plastic parts for fixing the 4 mm pin head glass. Wall thickness of frame shall be 2mm.Maximum possible size 1000mm x1000mm.(The cost is inclusive of all fixtures and separate charges for minor T&P's shall not be made)	Sqm	0.89	6538.10	Six Thousand Five Hundred ThirtyEight Paise Ten Only
75	Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, usage charges complete as per specifications. (KPWD SR 2023-24, V-II, Item No.12.11, Page No.99)	Cum	0.12	157848.80	One Lakh FiftySeven Thousand Eight Hundred FourtyEight Paise Eighty Only
76	Providing and fixing in position fully panelled Honne wood shutters for doors with stiles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and stiles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, usage charges complete as per specifications. (excluding cost of fixtures)	Sqm	4.20	8510.10	Eight Thousand Five Hundred Ten Paise Ten Only
77	Painting wood work with Deluxe Multi Surface Paint of required shade. Two coat applied @ 0.90L/10 m² over an under coat of primer applied @0.75 L/10 m² of approved brand and manufacture to give an even shade including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, sand papering and knotting , cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	8.40	157.80	One Hundred FiftySeven Paise Eighty Only
78	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two coat applied @ 0.90L/10 m² over an under coat of primer applied @ 0.80 L/10 m² of approved brand and manufacture including preparing the surface after thorougly cleaning oil, grease, dirt and foreign matter, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge.	Sqm	8.40	158.90	One Hundred FiftyEight Paise Ninety Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
79	Providing & fixing factory made PVC Door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2 No.s of 150mm long brackets of 15x15mm M.S Square tube, the entire door frame to be reinforced with 19x19mm M.S Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size complete as per manufacturers specification & direction of Engineer-in-charge.	m	11.40	363.50	Three Hundred SixtyThree Paise Fifty Only
80	Providing & fixing 30mm thick factory made rigid foam Prelam Panelled Door Shutters made from M.S. tube of 19x19mm, 19 gauge for stiles and 15x15mm for top & bottom rails, covered with heat moulded Prelaminated PVC C Channel of 5mm thick sheet & 30x50mm wide to form stiles & 5mm thick & 75mm wide Prelaminated PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick, 20mm wide cross PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet Prelaminated on either side fitted in the M.S. frame, Sealed to the stiles & rails with PVC Designer beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75mm Aluminium hinges. do- with both side prelam	Sqm	3.15	2704.90	Two Thousand Seven Hundred Four Paise Ninety Only
81	Providing and fixing flush door shutter made out of solid core block board type, well seasoned , chemicaly treated hard wood battens and internal frame with minimum 45 mm wide wooden frame alround door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door useing liquid phenol formaldehyde resin as per IS specifications 2202 (part-I) 1991. from manufacturer complete as per spcification. -do- 35 mm thick both side commercial	Sqm	3.15	3797.80	Three Thousand Seven Hundred NinetySeven Paise Eighty Only
82	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in- charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.) including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer in-Charge.	Kgs	84.00	645.90	Six Hundred FourtyFive Paise Ninety Only
83	Providing and laying water proofing treatment to the Roof with PU based single component elastomeric pure polyurethane based coating on New terrace/Chajjas/Sunken portion of WC:Bathroom, cold applied PU wate proofing membrane that is highly elastic with elongation greater than 400% and tensile strength greater than 2MPa as per ASTM D412. The waterproofing membrane to be applied in 2coats @ 1.6 kg/m2 to achieve final DFT (Dry Film Thickness) of 1mm including prime coat of epoxy primer @150 g/m2 and protection with 120gsm Geo-textile over the waterproofing membrane. The finished cost to include surface preparation, making coving at Junction, Bore Packing, treatment of construction joints completely as per specification..)	Sqm	120.00	934.00	Nine Hundred ThirtyFour Only

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
84	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	Each	4.00	5476.10	Five Thousand Four Hundred SeventySix Paise Ten Only
85	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : One urinal basin with 5 litre white P.V.C. automatic flushing cistern	Each	6.00	5041.50	Five Thousand FourtyOne Paise Fifty Only
86	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15mm C.P. brass pillar taps	Each	4.00	3488.50	Three Thousand Four Hundred EightyEight Paise Fifty Only
87	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS: 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	Ltr	1000.00	10.20	Ten Paise Twenty Only
88	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 25 mm nominal dia Pipes	m	60.00	359.90	Three Hundred FiftyNine Paise Ninety Only
89	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 32 mm nominal dia Pipes	m	60.00	452.80	Four Hundred FiftyTwo Paise Eighty Only
90	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber 150 x 100 mm size P type With Non Modular common burnt clay bricks of designation 3.5 & with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight or cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design:	Each	4.00	2921.40	Two Thousand Nine Hundred TwentyOne Paise Fourty Only
91	Providing and fixing Brass full way valve gate with C.I. wheel of approved quality (screwed end) : 25 mm nominal bore	Nos	2.00	621.40	Six Hundred TwentyOne Paise Fourty Only
92	Providing and fixing Brass full way valve gate with C.I. wheel of approved quality (screwed end) : 32 mm nominal bore	Nos	2.00	676.90	Six Hundred SeventySix Paise Ninety Only
93	Providing and fixing gun metal non- return valve of approved quality (screwed end) : 32 mm nominal bore Vertical	Nos	1.00	1047.00	One Thousand FourtySeven Only

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
94	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws, including excavation, refilling the earth or cutting of wall and making good the same complete wherever required : 25 mm nominal bore	Nos	4.00	743.70	Seven Hundred FourtyThree Paise Seventy Only
95	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws, including excavation, refilling the earth or cutting of wall and making good the same complete wherever required : 32 mm nominal bore	Nos	1.00	743.70	Seven Hundred FourtyThree Paise Seventy Only
96	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 g.	Nos	4.00	957.60	Nine Hundred FiftySeven Paise Sixty Only
97	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 100 mm diameter	m	50.00	329.40	Three Hundred TwentyNine Paise Fourty Only
98	Supplying heavy gauge PVC conduit pipe…… dia confirming to IS 2509 with suitable size benda, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall stone structure or rawl plugs in case of brick walls and cement plastering damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.	m	100.00	83.30	EightyThree Paise Thirty Only
99	Supplying…… mm dia 2mm/2.5mm thick heavy gauge PVC conduit pipe with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures. run with 18SWG GI fish wire wherever necessary.	m	100.00	80.30	Eighty Paise Thirty Only
100	Groove cutting in the wall supplying…..dia 2mm/2.5mm thick heavy gauge PVC Conduit Pipe with bends, metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out conduit wherever necessary.	m	100.00	81.30	EightyOne Paise Thirty Only
101	Supplying and fixing sheet metal box made out of 18 SWG sheet metal with necessary holes for cable/conduit entry as required with one coat of approved make etc.	Each	30.00	143.00	One Hundred FourtyThree Only
102	d)180x90x65mm	Each	30.00	165.70	One Hundred SixtyFive Paise Seventy Only
103	e)200x90x65mm	Each	30.00	184.20	One Hundred EightyFour Paise Twenty Only
104	Supplying and fixing PVC/metal conduit accessories.(3/5) b)25mm junction box	Each	20.00	57.60	FiftySeven Paise Sixty Only
105	c) 32mm deep junction box	Each	20.00	62.80	SixtyTwo Paise Eighty Only
106	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work cpmplete. a)12"x"12"x3" (330x300x76mm)	m	20.00	123.50	One Hundred TwentyThree Paise Fifty Only
107	b)12x9"x3" (300x228x76)	m	20.00	118.30	One Hundred Eighteen Paise Thirty Only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri G VENKATE GOWDA	
				Rate	Rate in words
108	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0sqmm (Earthwire) FRLS multistrand copper PVC insulated multi strand copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. compelete for each outlet. Short point upto 3Mtr from tapping point to out let via switch	Point	10.00	293.30	Two Hundred NinetyThree Paise Thirty Only
109	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0sqmm (Earthwire) FRLS multistrand copper PVC insulated multi strand copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. compelete for each outlet. b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch (Each point)	Point	10.00	405.40	Four Hundred Five Paise Fourty Only
110	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0sqmm (Earthwire) FRLS multistrand copper PVC insulated multi strand copper wire copper PVC insulated multi strand 2x1.5Sqmm copper wire (confirming to IS-694:and latest amendments) without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. a) Short point up to 3Mtr from tapping point to out let via switch box	Point	10.00	276.80	Two Hundred SeventySix Paise Eighty Only
111	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 2x1.5Sqmm (Phase & Neutral) & 1x1.0sqmm (Earthwire) FRLS multistrand copper PVC insulated multi strand copper wire copper PVC insulated multi strand 2x1.5Sqmm copper wire (confirming to IS-694:and latest amendments) without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch box (ELE SR 2023-24 Page-5, Item-2.2.2)	Point	10.00	390.00	Three Hundred Ninety Only
112	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. e) 6Moudule	Each	35.00	240.80	Two Hundred Fourty Paise Eighty Only
113	Supplying and fixing of modular switch & connected accessories on existing modular switch plate. (ELE SR 2023-24 Page-9, Item-3.6)	Each	25.00	105.00	One Hundred Five Only
114	Stepped Fan Regulator Two Module	Each	8.00	367.40	Three Hundred SixtySeven Paise Fourty Only
115	16A One Way Switch	Each	4.00	185.20	One Hundred EightyFive Paise Twenty Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.